

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:

Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Rice County, Sec. 19 Twp. 21 Rge. (E) 8 (W)
Location as "NE/CNW/KSW" or footage from lines C NW SW
Lease Owner Atlantic Richfield Company
Lease Name Jay J. Fitzpatrick Well No. 2
Office Address Box 521, Tulsa, Oklahoma 74102
Character of Well (completed as Oil, Gas or Dry Hole) gas
Date well completed 19
Application for plugging filed Mar. 18 1974
Application for plugging approved 19
Plugging commenced Mar. 25 1974
Plugging completed Mar. 28 1974
Reason for abandonment of well or producing formation depleted



Locate well correctly on above Section Plot

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3400 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	222'	8 5/8"	222'	none
			3399'	4 1/2"	3399'	2511.84

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3290' and dumped 4 sacks of cement.

Halliburton plugged well pumping in 3 sacks of hulls, 20 sacks of gel and 85 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 3 - 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON, ss.
Evelyn Roth

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth

Ellinwood, Kansas (Address)

Subscribed and sworn to before me this 2 day of April, 1974

George A. Meyer
Notary Public

My commission expires Feb. 10, 1975

GABRIEL-JONES INC.
WICHITA, KANSAS
DRILLERS WELL LOG

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1974
CONSERVATION DIVISION
Wichita, Kansas

JAY J. FITZPATRICK #2
C 11 1/4 SW 1/4 SECTION 19-21S-3W
RICE COUNTY, KANOK

COMMENCED: DECEMBER 12, 1964
COMPLETED: DECEMBER 23, 1964

OPERATOR - HENSLAIR OIL & GAS COMPANY

DEPTH		FORMATION	REMARKS
From	To		
0	95	SAND	
95	115	GREY SHALE	
115	222	RED OED	RAN 7 JOINTS 5-5/8" CASING, SET @ 222' w/ 275 BAGGS CEMENT
222	1330	RED OED	
1330	1400	SHALE & SHELLS	
1400	2040	LIME & SHALE	
2040	2947	SHALE	
2947	3035	LIME & SHALE	
3035	3045	LIME	
3045	3050	CHAY	
3050	3400	SHALE	RAN 107 JOINTS 4 1/2" CASING, SET @ 3399' w/ 175 BAGGS CEMENT
3400	TD.		

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN THE C 11 1/4 SW 1/4 SECTION 19-21S-3W, RICE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) US
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 23TH DAY OF DECEMBER, 1964, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USED AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires FEBRUARY 1, 1965