

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-159-20,986

LEASE NAME Willhaus

WELL NUMBER #1-5

SPOT LOCATION c w/2 SW NE

SEC. 5 TWP. 21 RGE. 7w (E)OR(W)

COUNTY Rice

DATE WELL COMPLETED 1982

PLUGGING COMMENCED 12-15-83

PLUGGING COMPLETED 1-11-84

TYPE OR PRINT

PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Gulfco Production, Inc.

ADDRESS 1900 W. Loop So. #1900 Houston, Tx. 77027

PHONE #( ) \_\_\_\_\_ OPERATORS LICENSE NO. \_\_\_\_\_

CHARACTER OF WELL \_\_\_\_\_  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Salina

Is ACO-1 FILED? \_\_\_\_\_ IF NOT, IS WELL LOG ATTACHED? yes

PRODUCING FORMATION \_\_\_\_\_ DEPTH TO TOP \_\_\_\_\_ BOTTOM \_\_\_\_\_ T.D. 3400

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	200	8 5/8		
		0	3398	4 1/2	2784	2794

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Sand off to 3150 Dump 4 sq. cement

B ridge hole at 325ft. Dump 5 yds. redl-mix

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Nicholas Casing Pulling LICENSE No. 6698

ADDRESS Box 206 Geneseo, Ks. 67444

STATE OF Kansas COUNTY OF Rice, SS.

Allen D. Nicholas (EMPLOYEE OF OPERATOR) OR  
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT  
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND  
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND  
CORRECT, SO HELP ME GOD.

(SIGNATURE) Allen D. Nicholas  
(ADDRESS) \_\_\_\_\_

SUBSCRIBED AND SWORN TO BEFORE ME THIS 12th DAY OF January, 1984

Tom L. Prickett  
NOTARY PUBLIC

MY COMMISSION EXPIRES: 12-25-84

RECEIVED  
STATE CORPORATION COMMISSION

JAN 13 1984


FORM CP-4  
REVISED 06-83



CONSERVATION DIVISION  
Wichita, Kansas

15-159-20986-0000

DAVIES & COMPANY INC  
 4501 E 31ST ST #101 #1-5 HARVEY D WILLHAUS 5-21-7W  
 TULSA, OK 74135 C W/2 SW NE  
 CONTR B & B DRILLING CTY RICE  
 GEOL TOM WESSELOWSKI FIELD WHERRY  
 1622 KB CM 10/10/80 CARD ISSUED 2/26/81 IP OIL WELL  
 1574 GL 15-159-20,986 MISS 3337-3352



SMP	TOPS	DEPTH	DATUM
HEEB SH	2698	-1076	
BR LM	2659	-1237	
LKC	2879	-1257	
CONG CHT	3334	-1712	
MISS CHT	3344	-1722	
MISS LM	3373	-1751	
RTD	3400	-1778	

8-5/8" 192/150sx, 4 1/2" 3299/150sx  
 DST (1) 3285-3350 (CONG)/NO DETAILS  
 RELEASED  
 DST (2) 3350-3370 (MISS)/NO DETAILS  
 RELEASED  
 MICT - CO, PF 45/3337-3352, FRAC W/  
 1000 GAL AC, 100,000# SD & 15,000  
 BBLs WTR, POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 31 1983

CONSERVATION DIVISION  
 Wichita, Kansas