


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Rice County, Sec. 12 Twp. 21 Rge. 7 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_

C NE NE  
Lease Owner F. G. Holl  
Lease Name Colle #1 Well No. \_\_\_\_\_  
Office Address Lyons, Kansas 67554  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plat

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 8/15/77 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 8/26/77 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation  
depleted

If a producing well is abandoned, date of last production  
\_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3492  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

STATE CORPORATION COMMISSION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>AUG 31 1977</u>				<u>8-5/8</u>	<u>163</u>	<u>none</u>
				<u>4 1/2"</u>	<u>3485 1/2</u>	<u>2319'</u>
CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded to 3450' and ran 3 sacks cement. Loaded hole with salt water, shot pipe at 3003', 2907', mud came in at 2907' to 2756'. Shot pipe at 2743', worked pipe loose and pulled 33 joints. Mud came in, couldn't work pipe loose, shot pipe at 1588', 1524', pumped into well to see if we could get circulation. Broke pressure down at 600 lbs., broke down to 100 lbs. and got circulation. Stopped circulating and mud came in, pumped mud out. Shot pipe at 1326', mud came in to 930', pumped mud out, shot pipe at 1228', pulled 38 joints. Pumped 3 sacks hulls, 20 sacks gel and 85 sacks 50/50 pos.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of August, 19 77

Margaret Melcher  
Notary Public.

My commission expires \_\_\_\_\_

