


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rice County. Sec. 19 Twp. 21 Rge. 7W (E) (W)
Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner M.D.I.C., Inc.
Lease Name Barber #1 Well No. _____
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 2/3/76 _____ 19____
Plugging completed 2/6/76 _____ 19____
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3475 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	215	none
				4 1/2"	3474	3002'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3360' and ran 4 sacks cement. Loaded hole, shot pipe at 2979', pulled 89 joints. Set rock bridge from 280 to 260' and ran 4 yards ready mix.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
CHASE, KANSAS
(Address)

Subscribed and sworn to before me this 9th day of February, 1976

My commission expires _____
NOTARY PUBLIC
MARGARET MELCHER
Rice County, Ks
My Comm. Exp. Feb. 15, 1979

[Signature]
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

FEB 12 1976

CONSERVATION DIVISION
Wichita, Kansas

RICHARD G. SMITH
 PETROLEUM GEOLOGIST

WICHITA 2, KANSAS
 602 Rule Bldg.

315 AM 5-9526
 REC. MU 2-6271

May 16, 1966

Re: Triple "D" Drilling Company
 No. 1 Barber
 C NE SW Sec. 19, 21s, 7w
 Rice County, Kansas

Triple "D" Drilling Company
 2400 North Main
 Hutchinson, Kansas

Gentlemen:

The following is my interpretation of the geological data derived from the samples, drilling time log, and Lane - Wells electrical log on the No. 1 Barber.

FORMATION TOPS

	Samples	Lane-Wells
Heebner	2764	2764
Toronto	2782	2782
Douglas	2794	2794
Brown Lime	2878	2878
Lansing	2949	2949
Base Kansas City	3301	3300
Shaley Conglomerate	3364	3360
Cherty Conglomerate	3372	3372
Mississippian	3402	3401
Kinderhook	3445	3444
Rotary Total Depth	3475	3475

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 5 1976
 CONSERVATION DIVISION
 Wichita, Kansas

REGIONAL STRUCTURAL CORRELATION

4 1/2 ~ 3.474

Formation	Triple "D" No. 1 Barber C NE SW 19-21-7	Pure No. 1 Swartz C NW NW 30-21-7 Oil	Pure No. 4 Swartz Est. C NE NE 25-21-8 Oil
Lansing	-1325	-1331	-1327
Mississippian	-1717	-1761	-1759
Kinderhook	-1320	-1330	--
Total Depth	-1851	-1345	-1337