


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Rice County, Sec. 12 Twp. 21 Rge. 7 (W)
Location as "NE/CNW/SW" or footage from lines Center north line N/2 SW/4
Lease Owner H.C. Bennett
Lease Name Nelson Well No. 1
Office Address 605 State St. Augusta, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 30, 19 56
Application for plugging filed August 2 19 56
Application for plugging approved " 3 19 56
Plugging commenced August 29 19 56
Plugging completed August 31 19 56
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation conglomerate sand Depth to top 3404 Bottom 3420 Total Depth of Well 3443 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	147'	none
				5 1/2"	3401 1/2'	2819'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back to 3390'. Dumped 6 sacks of cement. Shot pipe off at 2819'. Pulled pipe and mudded hole to 140'. Set rock bridge and dumped 15 sacks of cement. Finished mudding hole and dumped 5 sacks of cement at base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self
Address R R #4, Hutchinson, Kansas

STATE OF Kans. COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self
R. R. #4, Hutchinson, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of Sept., 19 56

My commission expires August 12, 1957

Dorothy E. [Signature]
Notary Public.

PLUGGING
FILE SEC. 12 T. 21 R. 7W
BOOK PAGE 86 LINE 29

9-10-1956

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Muldock, Wichita, Kansas


COPY

Company- HENRY BENNETT
Farm- Nelson No. 1

SEC. 12 T. 21 R. 7W
CNE SW

Total Depth. 3443'
Comm. 12-17-55 Comp. 12-30-55
Shot or Treated.
Contractor. Salina Drlg. Corp., Inc.
Issued. 8-25-56

County Rice
KANSAS



Elevation. 1632' DF

Production. Dry

Figures indicate Bottom of Formations.

surface soil-sand-red bed 70
shale-shells 655
red bed-shale 990
shale-lime 1360
lime 1422
shale-lime 1780
lime 1850
shale-lime 2565
lime 2703
lime-shale-sand 2805
lime-shale 3000
lime 3065
lime-shale 3120
lime 3275
lime-shale 3400
Conglomerate 3404
Conglomerate 3407 RTD
Drilled down Rainbow show
1' under the pipe, drilled
2 more feet no increase,
drilled down to 3443
Total Depth

TOPS:
Heebner 2707
Toronto 2723
Douglas 2726
Lansing 2932
Conglomerate 3400

Perf. fr 3395-3401' & fractured
w/3000# sand.

Installed tbg. & rods & after
pumping 1 bbl. oil per day was
abandoned.

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1966
CONSERVATION DIVISION
Wichita, Kansas