

STATE OF KANSAS
STATE CORPORATION COMMISSION

**Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas**

WELL PLUGGING RECORD

NORTH

**Locate well correctly on above
Section Plot**

Name of Conservation Agent who supervised plugging of this well.....DURKEE.....

Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

FILLED HOLE W/HEAVY MUD; SET WOOD PLUG @ 130';
CEMENTED W/15 SAX CEMENT: SET PLUG @ TOP: CEMENTED
W/ 10: SAX CEMENT.

RECEIVED
Conservation Div.
JUN 27 1940
STATION
CORPORATION
COMMISSION
MINNESOTA

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to..... J. D. FERRELL DRILLING CO., INC.
Address..... BOX 163, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF PARTON, ss.
J. W. Railsback (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Railsback
Box 163, Great Bend, Kans.
 (Address)

SUBSCRIBED AND SWORN to before me this 24th day of June, 1990

My commission expires.....Oct. 15. 1951

Notary Public.

22-5133-s 9-48-10M

PLUGGING
FILE SEC 9 T 21 R 7W
BOOK PAGE 101 LINE 35

WELL LOG

J. D. FERRELL DRILLING CO., INC.
AND S. E. LIKINS
THREDE #1

SW/4 Sec. 9; Twp. 21S; R7W
County: Rice

Total Depth: 3364'
Comm. 5-5-49 Comp. 5-15-49
Contractor: J.D. Ferrell Drilling Co., Inc.
Issued: 5-17-49

Elevation:
Production:

Casing: 8 5/8" 130' cemented with 125 sax bulk Cement
5 1/2" 3363 1/2' Cemented w/75 sx bulk cement

FIGURES INDICATE BOTTOM OF FORMATIONS:

cellar	5
sand	40
sand & shale	85
shale & shells	520
anhydrite	540
shale & shells	1065
shale & salt	1204
lime & shale	1526
shale & shells	1930
shale & lime	2920
lime	3035
lime & shale	3095
lime	3205
lime & shale	3363
Conglomerate	3364
Total Depth	3364

Tops:	
Conglomerate	3363
L. K. C.	2910
Total Depth	3364

We hereby certify this to be a correct and accurate log of
the above described well as shown on the daily Drilling
Reports.

J. D. FERRELL DRILLING CO., INC.,

By: *J. W. Hallsback*

J. W. Hallsback

JUN 27 1949

STATE OF KANSAS
COMMISSIONER OF CORRELATION
KANSAS

Subscribed and sworn to before me this 17th day of May, 1949.

My Commission Expires:

Oct. 15, 1951

Paul V. Sandgren
Notary Public

