

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21514-00-00
Spot: W2NW Sec/Twnshp/Rge: 4-21S-6W
3960 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: MITCHELL Well Number: 1A
County: RICE Total Vertical Depth: 3300 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

Production Casing Size: 4.5 feet: 3299 100 SX CMT
Surface Casing Size: 8.625 feet: 212 150 SX CMT

#107²⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/03/2003 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-5783

Proposed Plugging Method: Sand to 3180' and 4 sacks; 1000' and 35 sacks; 600' and 35 sacks' 270' to 0'.

RECEIVED
KCC DISTRICT #2
JUL 10 2003
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/03/2003 4:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded the bottom to 3180' and 4 sacks of common. Shot 4-1/2" casing off at 2280'. Pulled to 1000' and pumped 35 sacks. Pulled to 600' and 35 sacks. Pulled to 270' and circulated cement to surface.

Remarks: UNITED TICKET #4757 60/40 4%

Plugged through: CSG

District: 02

Signed

Jack Luthi
(TECHNICIAN)

INVOICE #

DATE 7-29-03

~~2004060092~~

2004060271