

5020286

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-159-21,324

SWNE, SEC. 4, T. 21 S, R. 6 (W)

4290 feet from N(S) section line

990 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5994

Lease Name Spohn Well # 1

Operator: Sher-Lon Corporation

County Rice 113.75

Name & Address P.O. Box 328

Well Total Depth 3500 feet

Sterling, Kansas 67579

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 209'-2105Ks

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, Kansas 67524

Company to plug at: Hour: 1:00 PM Day: 11 Month: April Year: 1986

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling (phone) 316 938 2457

were: Fill hole with sand to 3135' and cement with 5 sacks.

Set rock bridge on Fluid (450-55) and Fill hole with ready-mix Concrete to base of cellar.

Plugging Proposal Received by Arthur J. Roman
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:45 PM Day: 11 Month: April Year: 1986

ACTUAL PLUGGING REPORT Hole Filled with sand to 3135' and cemented with 5 sacks cement. Rock bridge set from 455' to 440' and hole cemented to base of cellar with 6 yards ready-mix concrete.

2700' of 5 1/2" casing recovered Tobias Bivickough Ticket #3085

Remarks: 5 1/2-3499-150 sacks Top Perf 3185-91
(If additional description is necessary, use BACK of this form.)

IN V OI D E D

(If you do not observe this plugging,

STATE CORPORATION COMMISSION

Signed Arthur J. Roman
(TECHNICIAN)

DATE 4-23-86

APR 22 1986

INV. NO. 13529

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM C
Rev. 6/4

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-159-21,324 (of this well) June 85
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Sher-Lon Corporation OPERATORS LICENSE NO. 5994

ADDRESS P O Box 328 Sterling, Ks. 67579 PHONE # (316) 278-3721

LEASE (FARM) Spohn #1 WELL NO. _____ WELL LOCATION SW NE NE COUNTY Rice

SEC. 4 TWP. 21s RGE. 6w of (W) TOTAL DEPTH 3500' PLUG BACK TO _____

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 209' CEMENTED WITH 200 SACKS

CASING SIZE 5 1/2" SET AT 3499' CEMENTED WITH 150 SACKS

PERFORATED AT 3420-22', 3430-32', 3448-50', 3460-62', 3185-91'

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL _____

Will plug according to rules & regulations of State of Kansas.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACC-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Immediately

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES & REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Don Hendricks PHONE # (316) 278-3721

ADDRESS Sterling, Ks. 67579

PLUGGING CONTRACTOR Kelso Casing Blling LICENSE NO. 6050

ADDRESS Box 347, Chase, Ks. 67524 PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]
(Operator or Agent)

RECEIVED

FEB 10 1986

DATE: February 7, 1986

Conservation Division
Wichita, Kansas

9