

2-070665

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-159-20,856.0000

SW NE NE, SECTION 3 TOWNSHIP 21 RANGE 6W

OPERATOR LICENSE # 4424 4290 FEET FROM S SECTION LINE
OPERATOR SMOKEY VALLEY RESOURCES 990 FEET FROM E SECTION LINE
NAME & 1325 WEST HIGHWAY 56
ADDRESS LYONS, KS 67554

LEASE NAME: MILLER #1
COUNTY: RICE 111.54
WELL TOTAL DEPTH: 3432'
PIPE: 5 1/2" @ 3430'
SURFACE CASING: 8 5/8" @ 241'

ABANDONED OIL WELL ☒ GAS WELL ☐ INPUT WELL ☐ SWD ☐ D&A ☐

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: QUALITY WELL SERVICE
ADDRESS: STERLING, KS LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 30 MONTH: 12 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: GEORGE S.
COMPANY NAME: SMOKEY VALLEY RESOURCES PHONE: (316) 257-5529
WERE: SAND TO 3300' AND 5 SACKS
35 SACKS AT 925'
35 SACKS AT 525'
295' TO 0'

PLUGGING PROPOSAL RECEIVED BY: MIKE WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (☒) PART (☐) NONE (☐)

COMPLETED: HOUR: 4:30 DAY: 30 MONTH: 12 YEAR: 1996

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3300' AND 5 SACKS OF COMMON. SHOT 5 1/2"
CASING OFF AT 2430'. PULLED TO 925', PUMPED 35 SACKS. PULLED TO 525', PUMPED
35 SACKS. PULLED TO 295'. CIRCULATED CEMENT TO SURFACE.

RECEIVED
KANSAS CORPORATION COMMISSION

REMARKS: 60/40 POZ 4% GEL ALLIED #4785 JAN 14 1997

CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

JACK LUTHI
JACK LUTHI

FORM CP-2/3
REV. 3/90

INVOICED

DATE

INV. NO.

47376

12-30 MAR 14 1997