

9-11

15
2-060222

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-113-21,229.0000

SE NE SW, SECTION 24 TOWNSHIP 21 RANGE 3W

OPERATOR LICENSE # 4569 1650 FEET FROM S SECTION LINE
2970 FEET FROM E SECTION LINE

OPERATOR Jay Boy Oil, Inc.
NAME & 224 E. Douglas, #425
ADDRESS Wichita, KS 67202

LEASE NAME: Wedel #1
COUNTY: McPherson
WELL TOTAL DEPTH: 3730' 121.22

CONDUCTOR PIPE: " @ '
SURFACE CASING: 8-5/8" @ 207'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Allen Drilling
ADDRESS: _____ LICENSE: 5418

COMPANY TO PLUG AT: HOUR: _____ pm DAY: 11 MONTH: 9 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Vince Schrepel
COMPANY NAME: Allen Drilling Company PHONE: _____

WERE: 35 sx cmt top Arb - 35 sx cmt thru DP 460' - 85 sx cmt thru DP 275' - 25 sx circ to surf from 60' - 10 sx R.H. - 10 sx WW - use 60/40 poz 2% gel.

PLUGGING PROPOSAL RECEIVED BY: Phil Worley

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 4:30p DAY: 11 MONTH: 9 YEAR: 1990

ACTUAL PLUGGING REPORT:
No Arb - 35 sx cmt thru dp @ 460' - 85 sx thru dp @ 275' - 25 sx cmt circ to surf from 606' - 10 sx cmt RH - 10 sx cmt water well - Halliburton #018534X 60/40 poz 2% gel

REMARKS: (Tool pusher believed there was some washout & suggested more cmt at 275'.)

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

R. Phil Worley
R. Phil Worley (AGENT)

DATE OCT 05 1990 OCT 9 1990

INV. NO. 29543 CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
REV. 3/90