

3-9

2-060294

46
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-159-22,103-0000

NE NE SE, SECTION 13 TOWNSHIP 21 RANGE 9W

OPERATOR LICENSE # 5210

2310 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR Lebsack Oil Prod. Inc.
NAME & ADDRESS P. O. Box 489
Hays, KS 67601

LEASE NAME: Axtell #2

COUNTY: Rice

WELL TOTAL DEPTH: 3400' 110.50

PIPE: 4-1/2" @ 3396'/150 sx

SURFACE CASING: 8-5/8" @ 216'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Kelso Casing Pulling
ADDRESS: P. O. Box 347, Chase, KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 9:00a DAY: 9 MONTH: 3 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Mike Kelso

COMPANY NAME: Kelso Casing Pulling PHONE: 316-938-2943

WERE: Sand to 3200' - cap w/4 sx cmt - shoot pipe - pull csg to 1100' & 35 sx cmt - pull csg to 700' & 35 sx - pull csg to 270' & circ cmt to surface.

PLUGGING PROPOSAL RECEIVED BY: District #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 11:30a DAY: 9 MONTH: 3 YEAR: 1992

ACTUAL PLUGGING REPORT:
Sanded to 3200' - capped w/4 sx cmt - shot pipe - pulled csg to 1100' & loaded hole - 35 sx cmt - pulled csg to 700' & 35 sx - pulled csg to 270' & circ 80 sx cmt to surface - perfs 3306-10' & 3322-26'.

REMARKS: Allied Cem #3185 - 60/40 poz 4% gel - rec 2626' of 4-1/2"

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE MAR 25 1992

INV. NO. 34825

R. Phil Worley
R. Phil Worley (AGENT)

FORM CP-2/3
REV. 3/90

aw