

12-8

2-

RECEIVED
KANSAS CORPORATION COMMISSION

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

JAN 14 1994

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-159-20,804-0000
C E/2 NW NW NE, SECTION 10 TOWNSHIP 21 RANGE 6W

OPERATOR LICENSE # 5734 4950 FEET FROM S SECTION LINE
2145 FEET FROM E SECTION LINE

OPERATOR CULVER & GROUNDS OIL PROP
NAME & BOX 793
ADDRESS MCPHERSON, KS 67460

LEASE NAME: MCKEE #1
COUNTY: RICE III. 22
WELL TOTAL DEPTH: 3422' PBSD 3415'

PIPE: 4-1/2" @ 3422'/100 SX

SURFACE CASING: 8-5/8" @ 250'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: KELSO CASING PULLING
ADDRESS: P O BOX 347, CHASE KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: PM DAY: 8 MONTH: 12 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: JOE LINKE
COMPANY NAME: KELSO CASING PULLING PHONE: 316-938-2943

WERE: SAND TO 3100' - CAP W/4 SX CMT - SHOOT PIPE - PULL CSG
TO 900' - 35 SX - PULL CSG TO 525' - 35 SX CMT - PULL
CSG TO 300' - CIRC TO SURF

PLUGGING PROPOSAL RECEIVED BY: DISTRICT 2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART (_____) NONE (_____)

COMPLETED: HOUR: 4:30P DAY: 8 MONTH: 12 YEAR: 1993

ACTUAL PLUGGING REPORT:
SANDED TO 3100' - CAPPED W/4 SX CMT - SHOT PIPE -
LOADED HOLE & PULLED CSG TO 964' - 35 SX - PULLED CSG
TO 352' - 145 SX CMT DID NOT CIRC - TAGGED CMT ON
12/9/93 - CMT 220', FLUID 125' - THERE SHOULD BE APP
450' CMT BELOW 220' - WELL WAS TOPPED OFF W/2-3/4 CU
YDS SLURRY CMT USING 1" PIPE - RECOVERED 2717'.

REMARKS: ALLIED #1646 60/40 POZ 4% GEL - PERFS 3399-3404' - PULLED
CSG TO 352', MISSING 525' PLUG.

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 1-19-94

INV. NO. 39731

HS
R. Phil Worley (AGENT)