

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-159-21,747.0000

SW, Sec. 5, T 21 S, R 7 W  
1650 feet from W section line  
1650 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9256

Lease Name Wilson Well # 1

Operator: Continental U.S. Exploration  
Name & Address 6350 L.B.J. Freeway, Suite 158  
Dallas, Texas 75240

County Rice  
Well Total Depth 3400 feet 110.50  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 7/8 feet 209

Attention: Bob Wagner

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Jay-Lan Corporation License Number 719

Address 207 W. 12th, Hays, Kansas 67681

Company to plug at: Hour: 1:00 PM Day: 4 Month: September Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Paul Nixon

(company name) Jay-Lan Corporation (phone) 913 628 3834

were: Pump 1 sack hulls, 15 sacks gel, 125 sacks 50/50 Poz. into 4 1/2"

Pump 10 gel and 75 cement into 8 7/8" - 4 1/2" annulus.

Signed [Signature]  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 7:00 PM Day: 24 Month: September Year: 1984

ACTUAL PLUGGING REPORT Pumped 4 gel and 100 sacks 50/50 Poz mix w/4 1/2  
gel into annulus. Pumped 1 hulls and 6 gel into 4 1/2" pressured to  
1200 PSI. and shut off. Drilled out gel and hulls to 1200'. Pressured  
up on 4 1/2" to 1500 PSI. (Perfs shut off). Ran tubing to 1440'. Pumped  
4 sacks gel. Pulled 2 Joints tubing and pumped 25 sacks 50/50 Poz mix  
w/4 1/2 gel @ 1380' Pulled tubing to 500' & circulated and filled hole to  
cellar w/60 sacks 50/50 Poz mix w/4 1/2 gel.

Remarks: No casing recovered. Allied Cementing Co. Tickets # 39161  
and 39165

RECEIVED  
STATE CORPORATION COMMISSION

10-9-84 OCT 0 9 1001

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

STATE CORPORATION COMMISSION  
Wichita, Kansas

Signed [Signature]  
(TECHNICIAN)

INVOICED

NOV 21 1984

DATE 10-17-84

INV. NO. 4389

FORM CP-2/3  
Rev. 9-82

9-24 OCT 25 1984