

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

2-070793

API Number: 15-159-22109-0000

NE NE NE SECTION 05 TWP 21 RANGE 7W

OPERATOR LICENSE #31925 4950' FEET FROM S SECTION LINE  
OPERATOR QUALITY WELL SERVICE 330' FEET FROM E SECTION LINE  
NAME & ADDRESS 249 BETH DRIVE  
STERLING, KS 67579

LEASE NAME WILHAUS C #1  
COUNTY RICE  
WELL TOTAL DEPTH 3418'  
PIPE 5 1/2" @ 3415' 111.00  
SURFACE CASING 8 5/8" @ 218'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: QUALITY WELL SERVICE

ADDRESS: 249 BETH DRIVE, STERLING, KS 67579 LICENSE: #31925

COMPANY TO PLUG AT: HOUR: 8:00 DAY: 7 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: RICHARD MCINTYRE

COMPANY NAME: QUALITY WELL SERVICE PHONE: (316) 727-3410

WERE: SAND TO 3400' AND 5 SACKS  
35 SACKS @ 1050'  
35 SACKS @ 600'  
270' TO 0

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 19 1998  
CONSERVATION DIVISION  
WICHITA, KS

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL  PART  NONE

COMPLETED: HOUR: 12:00 DAY: 7 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3400' AND 5 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 2940'. PULLED TO 1050' AND PUMPED 35 SACKS. PULLED TO 600' AND PUMPED 35 SACKS. PULLED TO 270' AND CIRCULATED CEMENT TO SURFACE.

REMARKS: ALLIED #2578, 60/40 POZ, 4% GEL.

I DID OBSERVE THIS PLUGGING.

JACK LUTHI

FORM CP-2/3  
REV. 3/90

10-20-98

60139