

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 10 1965

CONSERVATION DIVISION
Wichita, Kansas

5-10-1965

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name K & E Drilling, Inc.Complete Address: 719 Union Center, Wichita, KansasLease Name Robinson "A" Well No. # 1Location C SE SW Sec. 31 Twp. 30 Rge. 9 (E) (W)County Kingman Total Depth 4460'Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: K & E Drilling, Inc.Address: 719 Union Center, Wichita, Kansas License No. _____Operation Completed: Hour 10:15AM Day 7th Month May Year 1965

The Above well was plugged as follows:

228' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid
level in the hole was at 110'. 1st cementing plug and 1 sack of hulls
was pushed in fluid to 225', and cemented with 25 sacks, through the
drill pipe. Fluid in the hole was now at 39', 2nd cementing plug,
bridged solid with dry cement and hulls on fluid at 39', and cemented
with 10 sacks to the base of the cellar. Rat hole bridged and cemented
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICEDSigned: Archie Elving
Well Plugging SupervisorDATE 5/10/65INV. NO. 1138-W