

10 KANSAS 15.095.30120.00.00  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 10 1965

CONSERVATION DIVISION  
WICHITA, KANSAS

11-10-1965

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name Swingle "I" Well No. # 1

Location SW SE SE Sec. 16 Twp. 30 Rge. 9 (E) (W) W

County Kingman Total Depth 4365'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Garvey Drilling Company

Address: Route 2, Great Bend, Kansas License No.     

Operation Completed: Hour 4:15 PM Day 7th Month Nov. Year 1965

The Above well was plugged as follows:

207' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole  
was filled with drilling mud to 200', 1st cementing plug, bridged solid  
with dry cement and hulls on fluid at 200', and cemented with 25 sacks.  
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged  
solid with dry cement and hulls on fluid at 40', and cemented with 10  
sacks to the base of the cellar. Rat hole bridged and cemented with 2  
sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 11/10/65

INV. NO. 2159-41