

NO
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name Hunter "E" Well No. # 1

Location SW NW SW Sec. 13 Twp. 30 Rge. 9 (E) (W) W

County Kingman Total Depth 4298'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No.

Operation Completed: Hour 3:00 PM Day 19th Month July Year 1965

The Above well was plugged as follows:

214' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole
was filled with drilling mud to 200', 1st cementing plug, bridged
solid with dry cement and hulls on fluid at 200', and cemented with
25 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/21/65
INV. NO. 1501-W

Signed: Archie Elving
Well Plugging Supervisor