

Form CP-3
Rev. 6-26-62

70
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 9 1965

CONSERVATION DIVISION
Wichita, Kansas

4-9-1965

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sierra Petroleum Co., Inc.

Complete Address: 1015 Wichita Plaza, Wichita, Kansas

Lease Name Du Mars Well No. # 1

Location SE NW SE Sec. 11 Twp. 30 Rge. 9 (E) (W)W

County Kingman Total Depth 4346'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Sierra Petroleum Co., Inc.

Address: 1015 Wichita Plaza, Wichita, Kansas License No. _____

Operation Completed: Hour 5:00AM Day 8th Month April Year 1965

The Above well was plugged as follows:

242' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole
was filled with drilling mud to 240', 1st cementing plug, bridged
solid with hulls on fluid at 240', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with hulls on fluid at 40', and cemented with 10 sacks to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/9/65

INV. NO. 952-W

Signed: Archie Elving
Well Plugging Supervisor