

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Main, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Kingman County. Sec. 31 Twp. 30 Rge. 9 (E) 9 (W)
Location as "NE/CNW/SW" or footage from lines C SE SW
Lease Owner K & E DRILLING, INC.
Lease Name #1 Robinson-A Well No. 1
Office Address 719 Union Center Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-7-65 19
Application for plugging filed 5-12-65 19
Application for plugging approved 5-10-65 19
Plugging commenced 5-7-65 19
Plugging completed 5-7-65 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. Elving, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4460 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	228'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set wood plug and 1/3 sx. hulls @225'. Cemented thru drill pipe w/25 sx. heavy mud up to 40'. Set solid bridge @40' mixed 10 sx. sement up to base of cellar. Plug rat hole with 2 sx. Plugging completed 10:15 A.M.

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
H. L. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. L. Wilson
719 Union Center Building Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of May 1965

My commission expires August 30, 1965
Julene M. Bannon Notary Public.

DRILLER'S WELL LOG

OPERATOR: K & E DRILLING, INC.
719 Union Center Building
Wichita, Kansas

WELL NAME: #1 Robinson-A
LOCATION: C SE SW
Section 31-30-9W
Kingman County, Kansas

CONTRACTOR: K & E DRILLING, INC.
719 UNION CENTER BLDG.
WICHITA, KANSAS

CASING RECORD: 8-5/8" @228' w/250 sx.

COMMENCED: April 27, 1965

COMPLETED: May 7, 1965

ELEVATION: 1648 DF
1651 KB

ROTARY TOTAL DEPTH: 4460

PRODUCTION: D & A

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Sand	50
Red Bed	200
Shale and Shells	1755
Lime	2655
Lime and Shale	2815
Lime	3705
Lime and Shale	3810
Lime	4405
Chert	4421
Lime and Chert	4460

RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1965
CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

State of KANSAS
County of SEDGWICK ss:

I, H. L. Wilson of K&E DRILLING, INC. upon oath state
that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Subscribed and sworn to before me this 12th day of May 1965

My Commission expires: August 30, 1965

H. L. Wilson
Julene M. Bannon Notary Public.

