

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Take Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman

County. Sec. 16 Twp. 30 Rge. 9 (X) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE

Lease Owner Petroleum, Inc.

Lease Name Turley Well No. 1

Office Address Route 2, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed July 28 19 58

Application for plugging filed July 28 19 58

Application for plugging approved July 28 19 58

Plugging commenced July 28 19 58

Plugging completed July 28 19 58

Reason for abandonment of well or producing formation No producible zones

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel

Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 4400 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	252'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud up with heavy mud to 240' followed by a wooden plug and 1/2 sack hulls. Placed 20 sacks cement through drill pipe on to plug. Mud up to 40' followed by a wooden plug and 1/2 sacks hulls. Filled hole to base of well cellar with 10 sacks cement.

NOTE: Ran wire line and found cement at 57'. Placed 20 sacks cement in hole to base of well cellar. Job complete August 8, 1958

STATE OF KANSAS
AUG 7 8 1958
DIVISION
8-18-1958

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Co.
Address Route 2, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Don Searle (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle

Great Bend, Kansas


(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of August 19 58

[Signature]
Notary Public.

My commission expires July 11, 1960

PLUGGING
FILE SEC 16 Twp 30 R 9W
BOOK PAGE 119 LINE 9



Locate well correctly on above Section Plat

WELL LOG

COMPANY **PETROLEUM, INCORPORATED**

SEC. 16 T. 30S R. 9W

FARM **TURLEY**

NO. 1

LOC. SW, SW, NE


TOTAL DEPTH **4400'**

COUNTY **KINGMAN CO., KANSAS**

COMM. **July 15, 1958**

COMP. **JULY 28, 1958**

CONTRACTOR **GARVEY DRILLING COMPANY**



CASING **8 5/8" @ 252.75' W/200 sax.**

ELEVATION

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

90	Surface soil & sand
110	Red bed & shale
750	Red bed
1125	Shale & shells
1300	Salt
1350	Anhydrite
2055	Lime
2410	Shale & lime
2750	Shale & shells
2980	Shale
3229	Shale & lime
3240	Lime
3634	Lime & shale
4338	Lime
4376	Lime & chert
4400	Lime
4400	T. D.

STATE COMMISSION

AUG 18 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
 FILE SEC 16 T. 30 R. 9W
 BOOK PAGE 119 LINE 9

State of KANSAS }
County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 TURLEY well

Verne A. Morris
Subscribed and sworn to before me this 6th day of August 19 58

My Commission Expires: July 11, 1960

Jed A. Brown
NOTARY PUBLIC