

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County. Sec. 16 Twp. 20 Rge. 9w E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SW SW SE

Lease Owner E. H. Wood Jr.
Lease Name Swingle Well No. 1

Office Address 301 Farmers & Bankers Bldg. Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole)

Oil & Gas

Date Well completed September 1968

Application for plugging filed January 5 1981

Application for plugging approved 19

Plugging commenced January 9 1981

Plugging completed January 26 1981

Reason for abandonment of well or producing formation


Depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson
Producing formation Depth to top Bottom Total Depth of Well 4339'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	246'	none
				4 1/2"	4335'	3145'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole to 4300' set four sks. cement with bailer

Recovered 3145' of 4 1/2" casing

Set Rock Bridge at 260' Dumped four yds. ready mix cement to base of celler

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Voth Casing Pulling

STATE OF Kansas COUNTY OF Cowley, ss.

Walter Voth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth
715 South A Arkansas City Ks 67005
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of Jan, 1981

Milton Harris
Notary Public.

My commission expires



RECEIVED
STATE CORPORATION COMMISSION

FEB - 2 1981

CONSERVATION DIVISION
Wichita, Kansas

2-2-1981

WELL LOG
Swingle #1
C SW SW SE 16-30S-9W
Kingman County, Kansas

FROM	TO		Elevation: 1671 K.B.
0	255	Sand & red bed	
255	492	Red bed & shale	
492	1497	Red bed & shells	
1497	2675	Lime and shale	
2675	2813	Lime	
2813	3340	Lime and shale	
3340	3647	Shale and lime	
3647	4285	Lime	
4285	4337	Lime and chert	
4337		Total Depth	

STATE OF KANSAS

COUNTY OF BARTON ss

T. D. Sweetman, President of Sweetman Drilling, Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

T. D. Sweetman

T. D. Sweetman

Subscribed and sworn before me this 3rd day of September, 1968.

Reata J. Boyd

Notary Public

Barton County

