


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 4 Twp. 30 Rge. 9 (E) (W) X
C NW NE NE

Location as "NE/CNW%SW%" or footage from lines _____
Lease Owner Sierra Petroleum Co.
Lease Name Morrisse Well No. #1
Office Address 211 N. Broadway, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 2-7-66 19____
Application for plugging approved _____ 19____
Plugging commenced 2-12-66 19____
Plugging completed 2-15-66 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Herman E. Justus
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4255' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 4200'. Mixed and ran 3 sacks cement thru dump bailer.
Mudded hole to 250' - set 10' rock bridge. Filled hole with 3 1/4 yards ready-mix from 240' to base of cellar.

RECEIVED
FEB 17 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of February, 19 66

My commission expires 24 October 1968
Sidney D. Miller
Notary Public.

WELL LOG

COMPANY Sierra Petroleum Co., Inc.

SEC. 4 T. 30S^R. 9W

FARM Morisse NO. 1


LOC. NW NE NE

TOTAL DEPTH 4255'

COUNTY Kingman

COMM. 11-25-65 COMP. 12-5-65

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 251' w/200 sx

4 1/2" @ 4254' w/100 sx

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1966

CONSERVATION DIVISION
Wichita, Kansas

- 80' Shale and Sand
- 251' Shale and Red Bed
- 1420' Red Bed and Shale
- 1670' Lime with Shale
- 1765' Lime
- 2470' Lime and Shale
- 2610' Shale and Lime
- 2935' Lime with Shale
- 2990' Shale with Lime Streaks
- 3155' Lime
- 3335' Lime with Shale
- 3560' Shale and Lime
- 3585' Lime
- 3680' Lime with Shale
- 3981' Lime
- 4235' Lime and Shale
- 4255' Mississippi Chat
- 4255' RTD

State of Kansas }
County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Morisse No. 1 well.

Sam N. Stephens

Subscribed and sworn to before me this 30th day of December 19 65.

My Commission Expires: November 5, 1969

Richard Hoys
NOTARY PUBLIC