


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

AG
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

KIOWA County. Sec. 1 Twp. 30s Rge. 16 (#) (W)
Location as "NE/CNW/SW" or footage from lines APPROX. C NE SW
Lease Owner PETROLEUM, INC.
Lease Name ROBBINS Well No. 1
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed DECEMBER 15 19 60
Application for plugging filed DECEMBER 15 19 60
Application for plugging approved DECEMBER 15 19 60
Plugging commenced DECEMBER 15 19 60
Plugging completed DECEMBER 15 19 60
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production --- 19 --
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well MR. W. L. LACKAMP, JR.
Producing formation --- Depth to top --- Bottom --- Total Depth of Well 4655 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	603'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUDDER UP WITH HEAVY MUD TO 500' FOLLOWED BY A WOODEN PLUG. PLACED 20 SACKS OF CEMENT THROUGH DRILL PIPE ON TOP OF PLUG, MUDDER UP WITH HEAVY MUD TO 35' FOLLOWED BY WOODEN PLUG. PLACED 10 SACKS OF CEMENT ON TOP OF WOODEN PLUG TO BASE OF WELL CELLAR.

JAN 3 1961
Conservation Division
Wichita, Kansas
1-3-1961

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (Drilling Operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
ROUTE 2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 30TH day of DECEMBER, 1960

Arthur J. Wile
Notary Public.

My commission expires APRIL 14, 1963



WELL LOG 15.097.00100.00.00

COMPANY **PETROLEUM, INCORPORATED**

SEC. 1 T.30S R. 16W

FARM **ROBBINS** NO. 1


LOC. Approx. C-NE, SW

TOTAL DEPTH **4655'**

COUNTY **KIOWA CO., KANSAS**

COMM. **December 1, 1960** COMP. **December 15, 1960**

CONTRACTOR **GARVEY DRILLING COMPANY**



CASING **8 5/8" @ 603' w/450 sax.**

ELEVATION **1900' KB**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

30	Sand
50	Red bed
356	Red bed & gyp
800	Red bed
1800	Shale
1822	Anhydrite
2240	Shale & lime
2925	Lime & shale
3340	Shale & lime
3640	Lime & shale
3715	Lime
3848	Chalky lime & shale
3935	Lime
4000	Shale & sandy lime
4045	Lime & shale
4167	Lime
4207	Chalky lime & shale
4372	Lime
4555	Lime & shale
4585	Shale & lime
4605	Chert & lime
4640	Lime & shale
4647	Chert
4655	Cherty lime
4655	T. D.

JAN 5 1961
 CONSERVATION DIVISION
 Wichita, Kansas

State of KANSAS }
 County of BARTON } ss.

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 ROBBINS well

Verne A. Morris

Subscribed and sworn to before me this 23rd day of December 19 60

My Commission Expires: April 14, 1963

Arthur J. Miles
 NOTARY PUBLIC