


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Rush County. Sec. 12 Twp. 16 Rge. 16 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines NE/4 SE/4 SW/4
Lease Owner Shields Oil Producers, Inc.
Lease Name Brack Well No. 1
Office Address Shields Bldg., Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 25 1966
Application for plugging filed June 25 1966
Application for plugging approved June 25 1966
Plugging commenced June 25 1966
Plugging completed June 25 1966
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,510 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	270'	Cmtd. w/175 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole w/heavy mud
Halliburton pump 125 sax cement on mud to cellar

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Shields Drilling Co., Inc.
Address Shields Bldg., Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
R. J. Shields (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) RJ Shields
Shields Bldg., Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of July, 19 66

My commission expires May 26, 1967

Ruth Phillips
Notary Public.



Shields


15.16S.30101.00.00

Russell, Kansas

WELL LOG

Operator: Shields Oil Producers, Inc.
 Well: Brack #1
 Commenced: June 17, 1966
 Completed: June 25, 1966
 Contractor: Shields Drilling Co., Inc.

Well Description: NE SE SW
 Sec. 12-16S-16W
 Rush Co., Kansas



CASING RECORD
 Size Run Pulled

Elevation: 1,933' RB
 Treatment:

Production: D & A

Tops: Topeka 2,919'
 Heebner 3,154'
 Toronto 3,172'
 Lansing-KC 3,211'
 Ch. Congl. 3,466'
 Arbuckle 3,503'

..... Figures Indicate Bottom of Formations

Clay, post rock and shale	100'
Shale, sand, redbed and shale	830'
Shale	1,009'
Anhydrite	1,041'
Shale, shells and salt	1,315'
Shale and shells	1,700'
Shale and lime	2,000'
Lime	2,295'
Lime and shale	2,955'
Lime	3,510' RTD

NOTES

- DST #1 3,200'-40' Tool open 1 hr. w/good blow thruout. Recovered 195' muddy salt water w/few oil specks
IBHP 1,125#, IFP 32#, FFP 123#, FBHP 1,061#/20 min.
- DST #2 3,240'-60' Tool open 1 hr. w/weak blow for 5 min. Recovered 3' mud. IBHP 36#, IFP 36#, FFP 32# FBHP 32#/20 min.
- DST #3 3,451'-62' Tool open 15 min. w/weak blow for 3 min. Recovered 2' mud. IBHP(None taken) IFP 32#, FFP 32#
FBHP 1,903#/20 min.
- DST #4 3,504'-10' Tool open 1 hr. w/good blow thruout. Recovered 560' water. IBHP 1120#, IFP 32#, FFP 279#,
FBHP 1,107#/20 min.

RECEIVED
 STATE CORPORATION COMMISSION

JUL 6 1966

CONSERVATION DIVISION
 Wichita, Kansas