

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-067-20,615.00.00

LEASE NAME NORA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-16

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 16 TWP. 30S RGE. 36 (E) or (W)

COUNTY Grant

LEASE OPERATOR Mesa Petroleum Co.

ADDRESS P.O. Box 2009, Amarillo, Texas 79189

PHONE#(806) 378-1000 OPERATORS LICENSE NO. 5575

Date Well Completed P&A 11-27-85

Character of Well Dry

Plugging Commenced 11-27-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-27-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation NA Depth to Top _____ Bottom T.D. 6000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	trace-gas	5567	5618	8 5/8"	1855'	3'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plug # 1 2550-2750' 70 sx 60/40 Poz + 6% gel; Plug # 2 1740-1885' 40 sx 60/40 Poz + 6% Gel;
Plug # 3 570-700' 30 sx 60/40 Poz + 6% gel; Plug # 4 3'-40' 10 sx 60/40 Poz + 6% gel;
Plug # 5 10 sx in rathole and mousehole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mesa Petroleum Co. License No. 5575

Address P.O. Box 2009, Amarillo, Texas 79189

STATE OF Texas COUNTY OF Potter, ss.

Carolyn L. Cummings (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

12-4-1985 (Signature) Carolyn L. Cummings

RECEIVED
STATE CORPORATION COMMISSION
(Address) P.O. Box 2009, Amarillo, TX 79189

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 19 85

Aurina Pitts
Notary Public

My Commission Expires 8-6-89