

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Blitting Building
Wichita, Kansas

Rice County, Sec. 9 Twp. 21 Rge. (E) 7 (W)

NORTH

Locate well correctly on above
Section Plat

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
 Lease Owner Aylward Production Company
 Lease Name Theede Well No. 16
 Office Address 813 First National Bank Bldg., Wichita, Kansas.
 Character of Well (completed as Oil, Gas or Dry Hole) Oil
 Date well completed.....19.....
 Application for plugging filed.....19.....
 Application for plugging approved.....19.....
 Plugging commenced.....February 13 19 42
 Plugging completed.....February 22 19 42
 Reason for abandonment of well or producing formation.....
Oil exhausted.
 If a producing well is abandoned, date of last production.....19.....
 Was permission obtained from the Conservation Division or its agents before plugging was com-
 menced?.....

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
 Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3376 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from..... feet to..... feet for each plug set.
Total Depth 3376'; 8-5/8" casing set at 3356'; 16" OD set at 109'
Filled with mud to 3356'
Run 6 sacks cement to 3336'
Filled with mud to 150'
Bridged solid at 150' with rock
Run 20 sacks cement to 130'
Filled with mud to 15'
Cap with 6 sacks cement to cellar base
Mud used elevated from pit
Cement placed with sand line and dump bailer
Pulled 2089' of 8-5/8" casing
16" casing left in hole

FILE 9-21-7W
BOOK PAGE 14 OF 28

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....
Address.....

STATE OF Kansas, COUNTY OF S. Sedgewick, ss.
Wm. Irwin (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) General Oil Tool Company
 By [Signature]

SUBSCRIBED AND SWORN to before me this 23rd day of February

My commission expires January 19, 1943.

2-27-1942


THESE NO. 16

L. E. DOUGLASS
Hutchinson, Kansas

Sec 9-21-7
Rice County, Kansas

<u>Formation</u>	<u>Top</u>	<u>Bottom</u>	<u>Remarks</u>
sand and red rock	0	109	Set 109' Surface Pipe 16-OD
red shale and shells	109	609	
shale salt and lime	609	1050	
lime and shale	1050	1200	
lime shells and shale	1200	1325	
shale and shells	1325	1488	
lime and shale	1488	1631	
shale, lime and shells	1631	1773	
shale and lime	1773	1884	
shale	1884	2051	
shale & shells	2051	2290	
lime and shale	2290	2400	
lime (Topeka)	2400	2418	
lime	2418	2796	
lime and shale	2796	2879	
lime	2879	3317	K.O. lime - 2890 3356' of 8-5/8 Casing-107 jts. Cemented with 250 sax cement Well flowed steady from 3375 at rate of 275 bbls per hour.
lime and shells	3317	3356	
conglomerate	3356	3376	

9 21 7W
EJJK 14 28



THE AYLWARD PRODUCTION COMPANY
813 FIRST NATIONAL BANK BUILDING
WICHITA, KANSAS

February 26, 1942

State Corporation Commission,
800 Bitting Building,
Wichita, Kansas.


Dear Sirs:-

Enclosed herewith please find Well Plugging Record of the Theede
No. 16, properly executed, together with log of the well.

Yours very truly,

THE AYLWARD PRODUCTION COMPANY,

By:



Al Skalsky/jf
enc.

FILED
9 21 7W
BOOK 14 28

