

L. E. DOUGLAS
Theede No. 3

SEC. 9 T. 21 R. 7W.
NW SW SW

Total Depth. 3373'
Gom. 2-12-37 Comp. 3-2-37
Shot or Treated.
Contractor. L.E.Douglas
Issued. 5-8-37

County. Rice

CASING:
16" 103'
8-5/8" 3352'

Elevation.

Production. Pot. 4124 B.

Figures Indicate Bottom of Formations

sand and clay	70
sand	103
red rock and sand	185
shale	690
salt	980
shale	1014
brkn lime	1200
lime	1220
shale	1430
lime	1510
lime and shale break	1612
lime and shale	1615
shale	1757
shale and shells	1880
shale	1940
lime	1979
shale and shells	2200
lime	2240
shale	2318
lime	2371
lime and shale	2432
shale	2445
lime	2724
brkn lime	2795
shale	2821
shale and lime	2914
lime K.C.	3239
brkn lime and shale	3299
lime	3331
lime and shale	3352
conglomerate	3373
Total Depth.	

9 21 7W
14 21

Fill with heavy mud between all plugs
8 sax at 3360
20 sax at 150
8 sax at base of cellar

THE AYLWARD PRODUCTION COMPANY
813 FIRST NATIONAL BANK BUILDING
WICHITA, KANSAS

January 5, 1942

State Corporation Commission,
800 Bitting Building,
Wichita, Kansas.

Dear Sirs:-

Enclosed herewith please find Well Plugging Records, covering
Theede Wells Nos. 3 and 4, together with copies of log of wells.

Yours very truly,

THE AYLWARD PRODUCTION COMPANY,

By: *Al Skalsky*

Al Skalsky/jf
enc.

PLUGGING	
FILE	9-21374
BOOK	PAGE 14 LINE 21

