

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

Rice County, Sec. 9 Twp. 21 Rge. 7 (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW NE

Lease Owner Sterling Drilling Company

Lease Name Haxton #1 Well No.

Office Address Sterling, Kansas 67570

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 12/22/69 19

Plugging completed 12/24/69 19

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman

Producing formation Depth to top Bottom Total Depth of Well 3400 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	171'	none
				5 1/2"	3389'	2945'
RECEIVED STATE CORPORATION COMMISSION JAN 5 1969 CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, sanded hole to 3375' and ran 5 sacks of cement.  
Shot pipe at 2945', worked pipe loose and pulled 91 joints. Set  
bridge at 210' and rock to 200' with 30 sacks of cement. Mudded  
to 30', 10' rock bridge and ran 10 sacks cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.

Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss. NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN to before me this 26th day of December, 1969

My commission expires 2/15/71

Notary Public.

XERO COPY

XERO COPY

XERO COPY

XERO COPY

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- HAXTON #1  
LOCATED: W/2 NE/4 Section 9-21S-7W, Rice County, Kansas

OWNERS: Plains Exploration Company and Sterling Drilling Company  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 1, 1968  
COMPLETED: July 6, 1968

ROTARY TOTAL DEPTH: 3390'

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas

LOG

CASING RECORD

0 - 176 Sand  
176 - 1653 Lime and Shale  
1653 - 2280 Shale  
2280 - 3217 Lime and Shale  
3217 - 3380 Lime  
3380' - 3390 Chert

Ran 4 Jts. 8 5/8" surface casing,  
162' cemented at 176' K.B. with  
190 sacks HA5. Plug down at 11:55  
PM, 7-1-68.

Ran 10 1/2 Jts. 5 1/2" O.D. Casing  
3403' cemented @ 3389 with 75 sacks  
Pozmix salt saturated. Plug down  
at 8:10 AM, 7-6-68, by Howco.