

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rice County. Sec. 9 Twp. 21 Rge. (E) 7 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NW^c SW $\frac{1}{4}$ SE $\frac{1}{4}$
Lease Owner Mid Plains Oil Corporation
Lease Name John F. Snyder Well No. 3
Office Address Union National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 11-30 19 37
Application for plugging filed 12-22 19 41
Application for plugging approved 12-23 19 41
Plugging commenced 1/11/1942 19
Plugging completed 1/14/1942 19
Reason for abandonment of well or producing formation No longer productive

If a producing well is abandoned, date of last production September 19 41
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Conglomerate Depth to top 3360 Bottom 3378 Total Depth of Well 3378 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Conglomerate	Oil	3360	3378	15"	88'	None
				7"	3360'	2540'
				5 $\frac{1}{2}$ "	30'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from...feet to...feet for each plug set.

Mud & rock from 3378' to 3355'.
From 3355' to 3320', 6 sacks of cement
Mud from 3320' to 150'
From 150' to 130', 20 sacks of cement.
Dirt to 8' of base of cellar - 8 sacks of cement.

2-23-1942



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mid Plains Oil Corporation
Address 915 Union National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.

H. D. Lawyer (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

MID PLAINS OIL CORPORATION
(Signature) By H. D. Lawyer

915 Union National Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of February, 1942

My commission expires January 13, 1945
Haratha Starr Carpenter
Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg. Wichita, Kansas.

MID PLAINS OIL CORP.
Snyder No. 3

SEC 9 T. 21 R. 7W.
NW SW SE

Total Depth. 3378
Comm. 11-1-37 Comp. 11-30-37
Shot or Treated. 30 qts 3371 $\frac{1}{2}$ -3378
Contractor. Jack Garden.
Issued. 2-5-38

County Rice.

CASING.
12 $\frac{1}{2}$ " 88'
7" 3360'

Elevation.

Production. Pot. 289 B.

Figures Indicate Bottom of Formations.

Surface clay	11
sand	65
red bed	85
lime shells	88
red bed and shale	270
shale and shells	810
shale and lime	1030
broken lime	1480
shale and lime	1580
broken lime	1715
shale	1745
shale and lime	1810
broken lime	1860
shale and shells	1920
broken lime	1940
shale and shells	2055
shale and lime	2145
broken lime	2290
lime	2340
broken lime	2460
lime	2695
broken lime	2715
shale and lime	2765
broken lime	2883
lime and shale	2920
broken lime	3025
lime	3055
broken lime	3100
lime	3305
shale and lime	3359
red bed	3360
conglomerate	3378

Total Depth.

PLUGGING	
FILE	9 2107W
BOOK	PAGE 18 LINE 9

