


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

Rice County, Sec. 9 Twp. 21S Rge. 7W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

NE/4 SW/4 SW/4

Lease Owner Sher-Ion Corporation

Lease Name Theede #1 Well No.

Office Address 320 So. Broadway, Sterling, Kansas 67579

Character of Well (Completed as Oil, Gas or Dry Hole)

Date Well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 1/9/81 19

Plugging completed 1/13/81 19

Reason for abandonment of well or producing formation

Depleted

If a producing well is abandoned, date of last production

19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3435'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	184	None
				5-1/2"	3435	2987'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3200 and ran 5 sacks cement. Made shot at 2973. ~~RMXXWXXXKX~~ Pulled total of 72 joints. Plugged well with 3 sacks hulls, 20 sacks gel, 85 sacks 50/50 pos 4% gel, 8-5/8" plug. Plugging complete.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. Darrell Kelso*
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of January, 1981



My commission expires _____

Joan Kelso
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 1981
CONSERVATION DIVISION
Wichita, Kansas

EMPHASIS OIL OPERATIONS

P.O. Box 506
Russell, Kansas 67665

DRILLERS LOG

OPERATOR: Sherlon Corporation
212 S. Broadway
Sterling, KS

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, Kansas 67665

LEASE: Theede WELL: #1

LOCATION: C. SW $\frac{1}{4}$ SW $\frac{1}{4}$
SW $\frac{1}{4}$ Section 9-21S-7W
Rice County, Kansas

Total Depth: 3435'
Commenced: 4-18-80
Casing: 8-5/8" @ 184'
5-1/2" @ 3435'

Elevation:
Completed: 4-16-80
Status: Oil Well

RECEIVED
STATE OIL CORPORATION COMMISSION
APR 26 1980
CONSERVATION DIVISION
Wichita, Kansas

DEPTHS & FORMATIONS

(All measurements from K.B.)

Sand & Clay	40	Lime & Shale	2638
Shale	305	Shale & Lime	2916
Red Bed & Shale	1149	Lime & Shale	3366
Anhydrite	1180	Shale & Chert w/Lime (R.T.D.)	3435
Shale & Lime	1756		

STATE OF KANSAS)
COUNTY OF RUSSELL) ss

I, Joe K. Branum, of Emphasis Oil Operations, state that the above and foregoing is a true and correct log of the above captioned well.

Joe K. Branum

Joe K. Branum

Subscribed and sworn to before me this 29th day of April, 1980.
My Commission Expires: November 13, 1983.

Mary Anna Branum

Notary Public