


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rush County, Sec. 1 Twp. 16 Rge. 19W (E) X (W)
Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Terrel Drilling Company
Lease Name Miller Jimmurman Well No. 1
Office Address 754 E. Wichita Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 19____
Plugging completed November 5, 19 62
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3318' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

8 5/8" 198' circulated with cement.
Circulated hole with heavy mud, set cementing plug at 480',
displaced 25 sacks cement through drill pipe, heavy mud to
180', set plug and 20 sacks cement displaced through drill
pipe, heavy mud to 35', set plug, huls and filled to bottom
cellar with cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1964
3-11-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Terrel Drilling Company
Address 754 E. Wichita Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Joe K. Branson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branson
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of March, 1964

My commission expires 12-12-66

Notary Public.

15-165-19061-00-00

RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1964

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

OPERATOR: Terrel Drilling & Producing
Box 606
Russell, Kansas

CONTRACTOR: Company Tools

LEASE: Zimmerman #1

COMMENCED: October 29, 1962

LOCATION: NE NE SW, Sec. 1-16-19W
Rush County, Kansas

COMPLETED: November 4, 1962

DEPTHS & FORMATIONS

Surface Clay	195	Lime & Shale	2345
Shale	512	Shale & Lime	2395
Shale Sand & Anhydrite	1230	Lime & Shale	2628
Shale	1700	Shale w/ Lime	2785
Shale & Lime	2010	Lime & Shale (R.T.D.)	3318

STATE OF KANSAS)

COUNTY OF RUSSELL) ss...

Joe K. Branum, owner of Terrel Drilling and Producing, being first duly sworn on oath says: "That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct."

ORIGINAL SIGNED
JOE K. BRANUM

Joe K. Branum - TERREL DRILLING & PRODUCING

Subscribed and sworn before me this 10th day of March, 1964

Notary Public

My Commission Expires December 12, 1966