

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-165-21010-00-00

LEASE NAME Werth

WELL NUMBER 1

3630 Ft. from S Section Line

990 Ft. from E Section Line  
 NW SE NE

SEC. 1 TWP. 16S RGE. 19W (E) or (W)

COUNTY Rush

Date Well Completed 11-2-82

Plugging Commenced 3-5-88

Plugging Completed 3-10-88

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR DaMar Resources

ADDRESS Box 70 Hays, KS 67601

PHONE# (913) 625-0020 OPERATORS. LICENSE NO. 9067

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-10-88 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filled? Yes-by operator not, Is well log attached?

Producing Formation Arbuckle Depth to Top 3584 Bottom 3598 T.D. 3640

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	1184	8 5/8	10-25-82	
		0	3640	5 1/2	11-2-82	3-7-88 49 jts 2016 ft
		perfs	top	3180 -	3182	
			bottom	3579 -	3587	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
 Method of Plugging: Dumped in Sand w/dump baler to 3169 to cover perfs. Plugged with 5 sacks cement. Pulled on casing to 100,000#. Shot & pulled casing. Recovered 49 joints or 2016 ft of 5 1/2" casing. Went down 8 5/8" casing. Mixed 25 sacks ATL cement with 3 sacks hulls, then 175 sacks ATL cement with 2 sacks hulls. Maximum pressure 800#. Shut in pressure 300# psi.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bills Well Service License No. 83901N

Address Box 37 Codell, KS 67630

STATE OF Kansas COUNTY OF Ellis, ss.

Gary Geist

(Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have known the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 19<sup>th</sup> day of April, 19 88

My Commission Expires: \_\_\_\_\_

DONALD J. SIMONS  
 Ellis County, Ks.  
 Notary Public  
 Opt. Exp. 2-11-91

RECEIVED  
 STATE CORPORATION COMMISSION

APR 21 1988