



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Orville Powell of Braden-Deem, Inc. has this

date requested permission to plug the following described well:

Mr. Powell guarantees payment of the plugging fee.

Operator's full Name: Jayhawk Oil Company

Complete Address: 103 One-Twenty Bldg., Wichita, Kansas 67202

Lease Name: Theede Well No. 1

Location: SE SE Sec. 4 Twp. 21 Rge. 7 (E)(W) X

County: Rice Total Depth 3397' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Powell was instructed to plug the well as follows:

Fill hole with sand to 3375' and cement with 5 sacks cement.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1968
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

[Signature]
Conservation Division Agent