



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

February 10, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. L. B. Smith of Flowers Well Servicing, Inc. has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Commercial Oil Company

Complete Address: 5252 N. Broadway, Wichita, Kansas 67219

Lease Name: Rainey Well No. 1

Location: SWc SW Sec. 3 Twp. 21 Rge. 6 ~~(E)~~ (W) X


County: Rice Total Depth 3461' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

Push plug to 3170'. Fill hole with sand to 3160' and cement with 6
sacks cement. Fill hole with mud to 275'. Set rock bridge from 275'
to 260' and cement hole to base of collar with 7 yards ready-mix
concrete.

Very truly yours,


Conservation Division Agent