



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

July 17, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock,
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Art Lamb of Art Lamb Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Commercial Oil Company

Complete Address: 5252 N. Broadway, Wichita, Kansas 67219

Lease Name: Rainey Well No. 6

Location: NW NE SW Sec. 3 Twp. 21 Rge. 6 ~~(E)~~ (W) X

County: Rice Total Depth 3419' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 3375' and cement with 6 sacks cement.

Fill hole with mud to 215'. Set rock bridge from 215' to 200' and

cement hole to base of cellar with 6 yards ready-mix concrete.

Very truly yours,

Conservation Division Agent