

State of Kansas



15.159.05234.0000

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

July 30, 1969

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 14 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Art Lamb of Art Lamb Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Pat Simmons

Complete Address: 5252 N. Broadway, Wichita, Kansas 67219

Lease Name: Rainey Well No. 2

Location: SW NE SE Sec. 3 Twp. 21 Rge. 6 (E) (W) X

County: Rice Total Depth 3381' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lamb was instructed to plug the well as follows:

(Cement had been circulated between 5 1/2" and 7" casing--no recovery.)

Fill hole with sand to 3375' and cement with 5 sacks cement.

Set rock bridge from 210' to 200' and cement hole to base of cellar with

1 1/2 yards ready mix concrete (inside 5 1/2" casing.) Fill 20" surface pipe

with ready mix concrete.

Very truly yours,


 Conservation Division Agent