



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GIAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg.
 WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 2 1968
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

November 21, 1968

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Ed. Schonoff of Pipe Pullers, Inc. has this

date requested permission to plug the following described well:

Mr. Schonoff guarantees payment of the plugging fee.

Operator's full Name: H. L. Herbel

Complete Address: P.O. Box 327, Chase, Kansas 67524

Lease Name: L. J. Driver Well No. 3

Location: C SE NW Sec. 25 Twp. 21 Rge. 8 (E)(W) X

County: Rice Total Depth 3475' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Schonoff was instructed to plug the well as follows:


Fill hole with sand to 3365' and cement with 3 sacks cement.

Fill hole with mud to 260'. Set rock bridge from 260' to 250' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set

rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


 Conservation Division Agent