

State of Kansas



15.159.06635.0000

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 4 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Ed. Schonoff of Pipe Pullers, Inc. has this date requested permission to plug the following described well:

Mr. Schonoff guarantees payment of the plugging fee.

Operator's full Name: H. L. Herbell

Complete Address: P.O. Box 327, Chase, Kansas 67524

Lease Name: R. M. Culbertson Well No. 1

Location: NW NW SW Sec. 25 Twp. 21 Rge. 8 (W) X

County: Rice Total Depth 3421' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Schonoff was instructed to plug the well as follows:

Fill hole with sand to 3350' and cement with 5 sacks.

Fill hole with mud to 250'. Set rock bridge from 250' to 240' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


 Conservation Division Agent