

State of Kansas



15.159.06639.0000

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

December 4, 1968

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ed Schonoff of Pipe Pullers, Inc. has this
date requested permission to plug the following described well:

Mr. Schonoff guarantees payment of the plugging fee.

Operator's full Name: H. L. Herbel

Complete Address: P.O. Box 327, Chase, Kansas 67524

Lease Name: Swartz Estate Well No. 1

Location: SW NE NESW Sec. 25 Twp. 21 Rge. 8 (E) (W) X

County: Rice Total Depth 3475' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Schonoff was instructed to plug the well as follows:

Fill hole with sand to 3350' and cement with 5 sacks cement.

Fill hole with mud to 260'. Set rock bridge from 260' to 250' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1968
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Conservation Division Agent