



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission  
CONSERVATION DIVISION  
(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

December 3, 1962

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

DEC 10 1962

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Olin Kelso of Sterling Drilling Co. has this

date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Co.

Complete Address: Box 127, Sterling, Kansas

Lease Name: Wilkey Well No. 1

Location: C SW NE NW Sec. 10 Twp. 21 Rge. 8 (E) (W) X

County Rice Total Depth 3330' Oil Well         

Gas Well X Input Well          SWD Well          D & A          Lost Hole         

Mr. Kelso was instructed to plug the well as follows:

(Well dead) Fill hole with sand to 3270' and cement with  
5 sacks. Fill hole with mud to 210'. Set rock bridge  
from 210' to 200' and cement with 20 sacks. Fill hole  
with mud to 40'. Set rock bridge from 40' to 30' and  
cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent