



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION  
 (Oil, Gas and Water)  
 500 Insurance Bldg.  
 WICHITA, KANSAS 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 22 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

October 19, 1968

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Olin Kelso of Sterling Drilling Company has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: HINKIE OIL COMPANY  
Sterling Drilling Company  
1016 UNION CENTER WICHITA,  
 Complete Address: P.O. Box 129, Sterling, Kansas 67201

Lease Name: Yeakel Well No. 1

Location: W/2 E/2 NE Sec. 31 Twp. 21 Rge. 8 (E) (W) X

County: Rice Total Depth 3462' Oil Well     

Gas Well      Input Well      SWD Well      D & A      Lost Hole X

Mr. Kelso was instructed to plug the well as follows:

Pump 75 sacks cement through 5 1/2" casing to 3000'.  
Fill hole with mud to 245'. Push plug and 1/2 sack hulls to 245' and  
cement hole with 25 sacks through drill pipe. Fill hole with mid  
to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks  
cement. Bridge rathole and cement with 2 sacks.

5 1/2" casing shot off at 2473' and  
pulled with rotary drilling rig.

Very truly yours,

[Signature]  
 Conservation Division Agent