



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

October 2, 1970

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 7 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Paul Stephens of Rains & Williamson Oil Co., Inc this date requested permission to plug the following described well:

Mr. Stephens guarantees payment of the plugging fee.

Operator's full Name: Adair Oil Company

Complete Address: Box 7011, Wichita, Kansas 67201

Lease Name: Ross-Hurley Well No. 1

Location: N/2 NE NE Sec. 15 Twp. 21 Rge. 9 (E) (W) X

County: Rice Total Depth 2967' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Stephens was instructed to plug the well as follows:

Fill hole with heavy mud. Push plug to 450'. Pump 40 sacks cement  
through drill pipe at 450'. Pump 20 sacks cement through drill pipe  
at 200'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks  
cement. Bridge rathole and cement with 2 sacks cement.

(Orders by Don Truan)

Very truly yours,

  
Conservation Division Agent