



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

August 20, 1969

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 26 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: J. K. Fortner & W. A. Snyder

Complete Address: Box 97, Ellinwood, Kansas 67526

Lease Name: Theede Well No. 1

Location: NW NW SE Sec. 4 Twp. 21 Rge. 7 ~~(E)~~ (W) X

County: Rice Total Depth 3372' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3329' and cement hole with 5 sacks cement.

Bail hole to 210'. Set rock bridge from 210' to 200' and cement hole

with 35 sacks cement. Fill hole with mud to 40'. Set rock bridge from

40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


 Conservation Division Agent