

15009-16131-0000

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 52-32

LOCATION SW-NE-SE

SEC. 8 TWP. 16 RGE. 13W

Dry Hole Abandoned Oil Well ☒ Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 2 Lease Bitter

Operator Lawrence Supply Co. Address 1306 Cleveland St Bend Kans.

Field County Barton

Total Depth 3408' Feet.

Plugging Contractor West Supply Co. Inc

Plugging Contractor's License No. 14

Address Chase Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 5/8" @ 380' c.w.c. 5 1/2" set 3403' 4/125 x
Cm. Sanded hole to 3390 dumped 5 x Cm. No record
on perf. Set plug at 3000' dumped 2 x Cm.
Shot off and pulled 5 1/2" casing. Mudded hole
to 275' set rock bridge and run 20 x Cm.
mud to 35' rock bridge and 10 x Cm to
base of cellar

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1954

CONSERVATION DIVISION
Wichita, Kansas

Warren H. Harner
District Conservation Agent

Date Aug 18, 1954

