

P KANSAS  
STATE CORPORATION COMMISSION

1500916132-0000

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

AUG 23 1965

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Herndon Drilling Company

Complete Address: Box 526, Lyons, Kansas

Lease Name Bitter Well No. # A 3

Location NE SE SE Sec. 8 Twp. 16 Rge. 13 (E) (W) W

County Barton Total Depth 3396

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply

Address: Great Bend, Kansas License No. 574

Operation Completed: Hour 3 P.M Day 19 Month 8 Year 1965

The Above well was plugged as follows:

8 5/8" 280' Cwc.  
Sanded hole back to 3255' & dumped 4 sax cement with dump bailer. Pulled  
pipe. Mudded hole to 280'; set rock bridge & displaced 4 yds. Ready-mix  
cement, cementing from 270' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Low Trean  
Well Plugging Supervisor

DATE 8/23/65

INV. NO. 1669-W

WELL LOG OF BITTER #3

Spudding date: 4/3/47  
 Date casing set: 4/14/47  
 Date completed: 4/18/47

Location:  
 Section 8, Twp. 16, Rge. 13,  
 Barton County, Kansas

TOTAL DEPTH 3397'

| FROM | TO          | FORMATION        | REMARKS   |
|------|-------------|------------------|---|
| 0    | 530         | Shale and shells |   |
| 530  | 555         | Anhydrite        |   |
| 555  | 895         | Shale and shells |   |
| 895  | 930         | Lime             |   |
| 930  | 1230        | Shale and shells |   |
| 1230 | 1590        | Salt and shale   |   |
| 1590 | 1740        | Shale and shells |   |
| 1740 | 1975        | Shale and lime   |   |
| 1975 | 2030        | Lime             |   |
| 2030 | 2035        | Lime and shale   |   |
| 2035 | 2215        | Shale and shells |   |
| 2215 | 2380        | Lime and shale   |   |
| 2380 | 2500        | Shale and shells |   |
| 2500 | 2780        | Shale and lime   |   |
| 2780 | 3155        | Lime             |   |
| 3155 | 3215        | Broken lime      |   |
| 3215 | 3235        | Lime and shale   |   |
| 3235 | 3373        | Lime             |   |
| 3373 | 3395        | Shale            |   |
| 3395 | 3397        | Arbuckle         |   |
| 3397 | TOTAL DEPTH |                  | Run 105 jts. 14# casing and<br>6 jts. 15-1/2# casing. Cemented<br>with 200 sacks bulk cement. |

Subscribed and sworn to before me this  
 2nd day of May, 1947.

I certify the above and foregoing to  
 be a true and exact copy of the original  
 driller's log on the Bitter #3 well.

*Philetus J. Moore*  
 Notary Public

*W. E. Ray*

My commission expires: 11/4/50

RECEIVED  
 CONSERVATION DIVISION  
 Topeka, Kansas  
 OCT 27 1965