

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-30072-00-00
Spot: SESENWNW Sec/Twnshp/Rge: 24-25S-8E
4125 feet from S Section Line, 4125 feet from E Section Line
Lease Name: WELSH C Well #: 2
County: GREENWOOD Total Vertical Depth: 2461 feet

Operator License No.: 32701
Op Name: C & G DRILLING, INC.
Address: 701 E. RIVER ST.
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2459		100 SX
SURF	8.625	206		130 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/08/2017 10:00 AM
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.
Proposal Rcvd. from: TIM GULICK Company: Phone: (620) 583-4306

Proposed Plugging Method: As per state requirements

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL
Date/Time Plugging Completed: 11/08/2017 2:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Spotted 10 sxs cement @ 2400', w/dump baler, cut off casing @ 945', pumped 20 sxs cement, pulled casing out, ran tubing to 250', pumped 80 sxs cement to surface, gel spaceers between cement plugs,

Perfs:

RECEIVED
KCC DIST #3
NOV 20 2017
CHANUTE, KS

MT

INVOICED
DEC 10 2017

Remarks:

Plugged through: TBG

District: 03

Signed

Mike Heffern
(TECHNICIAN)

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



15-073-30072
Cement or Acid Field Report
Ticket No. **3578**
Foreman Steve Reed
Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
11-8-17	1037	Welsh #C2	24	25	8	Greenwood	KS	
Customer <u>C + G Drilling</u> Mailing Address <u>701 E River</u> City <u>Eureka</u> State <u>Ks</u> Zip Code <u>67045</u>			Safety Meeting		Unit #	Driver	Unit #	Driver
					102	Rick		
					110	Taser		

Job Type PTA Hole Depth _____ Slurry Vol. _____ Tubing 2 3/4
Casing Depth 1 Hole Size _____ Slurry Wt. _____ Drill Pipe _____
Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: Rig up to 4 1/2 casing Break circulation w/ Fresh water
Mix 200# Gel Flush Spot 200# cement At 915'. Pull out 4 1/2 casing
Run 250' 2 3/4 tubing. Break circulation w/ Freshwater Mix 80#/s
250' to surface & Top well off. Job complete Rig down

Thank you

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C1052	1	Pump Charge	525.00	525.00
		Mileage <u>N/C</u>	-	-
C203	100 sks	60/40 Permox Cement	12.75	1275.00
C206	340#	Gel 4 1/2	.20	68.00
C206	800#	Gel Flush	.20	160.00
C108A	4.2500	700 Mileage back Trucks	M/C - 1/2	193.00
590 < 111.91 > #212126			Sub Total	2083.00
			Sales Tax	156.23
Authorization <u>by Willy</u> Title <u>Co Rep.</u>			Total	2239.23

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.