

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-00513-00-00
Spot: NENESE Sec/Twnshp/Rge: 15-22S-15W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: LOVETT Well #: 1
County: PAWNEE Total Vertical Depth: 3970 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3674		
CIBP		3740		
PROD	5.5	3958	0	WITH 100 SX CMT
SURF	8.625	225		WITH 185 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/20/2017 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: CHRIS SCHOENHOFER Company: CHARTER ENERGY Phone: (620) 793-9090

Proposed Plugging Method: PUMP 200# HULLS & CMT TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/22/2017 1:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

4/28/17: PERFORATE AT 918' -20' WITH 4 SHOTS. SQUEEZE 100 SX CMT. 10/20/17: CMT THROUGH 5 1/2" CASING WITH 400 SX CMT & 600# HULLS. HOLE FULL & PRESSURED UP TO 500 PSI. TIE ONTO BACKSIDE & PRESSURE UP TO 500 PSI. CASING REMAINING FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
3625	3671		


Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

INVOICED
DEC 1 0 2017

District: 01

Signed



(TECHNICIAN)

RECEIVED
OCT 31 2017
KCC DODGE CITY

51A