

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-23588-00-00
Spot: SESENESE Sec/Twnshp/Rge: 5-27S-6E
1344 feet from S Section Line, 300 feet from E Section Line
Lease Name: BEADLES Well #: W-3
County: BUTLER Total Vertical Depth: 3149 feet

Operator License No.: 6655
Op Name: CRAWFORD, GARRY F. DBA CRAWFO
Address: PO BOX 727
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2810		
PROD	5.5	3149		125 SX
SURF	8.625	211		125 SX
T1	2.875	2747		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/07/2017 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: BRANCE CRAWFORD Company: _____ Phone: (316) 323-5513

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 11/07/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2673', DUMP BAILED 4 SXS CEMENT ON TOP OF SAND. PRESSURED CASING @ 200#, HELD OK. RIH ON WIRELINE, PERFERATED SQUEEZE HOLES 260'-261' (4 HOLES). SWEDGED INTO 5 1/2" CASING, QES MIXED & PUMPED 90 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #54693.

Perfs:

Top	Bot	Thru	Comments
3136	3139	CSG	
2780	2780	CSG	set plug
2750	2756	CSG	

INVOICED

DEC 13 2017

Remarks: DENIED TA/ LENGTH OF TMIE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

✓