

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19378-00-00
Spot: NESENE Sec/Twnshp/Rge: 19-29S-8E
4288 feet from S Section Line, 531 feet from E Section Line
Lease Name: SHINN Well #: 24
County: BUTLER Total Vertical Depth: 2792 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2768		45 SX
SURF	10.75	26		35 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/18/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICK HART/HAYS WILSON Company: _____ Phone: (405) 526-0111

Proposed Plugging Method: AS PER KCC RULES & REGS. CIBP @ 2750' W/7 SXS. PERF & CIRCULATE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 10/19/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/BIT & TUBING. CIRCULATED HOLE CLEAN @ 2770'. LAYED DOWN 1 JOINT, W/TUBING @ 2740', QWS MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL 2% CC & 100# HULLS & DISPLACED IN CASING. PERFORATED SQUEEZE HOLES @ 250'-251' (4 HOLES). RIH W/TUBING @ 260', QWS MIXED & PUMPED 95 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TUBING, SWEDGED INTO CASING, QWS MIXED & PUMPED 150 SXS 60/40 POZMIX 4% GEL. CEMENT DID NOT CIRCULATE. WAITED 2 HOURS, RIH W/TUBING @ 270', QWS MIXED & PUMPED 55 SXS 60/40 POZMIX 4% GEL 3% CC & 100# HULLS & DISPLACED IN CASING. WAITED 2 HOURS, RIH W/TUBING @ 65', QWS CIRCULATED 40 SXS 60/40 POZMIX TO SURFACE. RIH W 1" IN BACKSIDE - 220'. QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. 10-19-2017 TOPPED WELL BACK TO SURFACE WITH 25 SXS.

Perfs:

Top	Bot	Thru	Comments
2678	2792	OH	

INVOICED

Remarks: COMPLIANCE - DENIED TA

DEC 13 2017

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

SK