

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-04227-00-00
Spot: SESENW Sec/Twnshp/Rge: 22-18S-11W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: OBERLE B Well #: 1
County: BARTON Total Vertical Depth: 3349 feet

Operator License No.: 34935
Op Name: DEXXON, INC.
Address: P O BOX 348
KIEFER, OK 74041

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3315		150 SX
SURF	8.625	300		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/03/2017 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: BRIAN OBERLE Company: DEXXON, INC. Phone: (620) 793-2299

Proposed Plugging Method: Ordered 200 sx common cement w/3% cc, 200 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/06/2017 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 590' and 250'. Ran tubing to 3250' and pumped 13 sx gel followed by 50 sx common cement w/3% cc and 200 # hulls. Pump truck broke down. Shut down for the day.
11/06/2017 - Ran tubing to 1400' and pumped 80 sx common cement w/3% cc and 200# hulls.
Pulled tubing to 600'. Circulated cement to surface on casing with 75 sx cement. Shut valve on casing and pulled tubing. Topped off with 5 sx cement.

GPS: 38.47214 -098.52764

Perfs:

Top	Bot	Thru	Comments
3039	3047		
3016	3031		

INVOICED
DEC 13 2017

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

NOV 20 2017

CONSERVATION DIVISION

NOV 06 2017